

## STATE OF UTAH

FORM 3

DEPARTMENT OF NATURAL RESOURCES  
DEPARTMENT OF OIL, GAS AND MININGAMENDED REPORT ☐  
(highlight changes)

## APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: ML 11004	6. SURFACE: <del>STATE</del> Fed.
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
2. NAME OF OPERATOR: <b>WEXPRO COMPANY</b>		8. UNIT or CA AGREEMENT NAME: ISLAND UTU063026X	
3. ADDRESS OF OPERATOR: P.O. BOX 458 CITY ROCK SPRINGS STATE WY ZIP 82902		PHONE NUMBER: 307 382-9791	9. NAME OF WELL and NUMBER ISLAND UNIT WELL NO. 89
4. LOCATION OF WELLS (FOOTAGES) AT SURFACE: 606579X 4424975Y 39.970102 -109.752008 AT PRODUCING ZONE: 606515X 4425391Y 1670' FSL, 1770' FWL 39.973864 NE SW 109.752488		10. FIELD AND POOL, OR WILDCAT: ISLAND, WASATCH Natural Butte	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: APPROXIMATELY 32 MILES FROM VERNAL, UTAH		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SE SW 2-10N-19E, SLB&M	12. COUNTY UINTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1670' (BHL)		16. NUMBER OF ACRES IN LEASE: 645.79	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: N/A
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1400'		19. PROPOSED DEPTH: 8,620' (MD) 8,326' (TVD)	20. BOND DESCRIPTION: Nationwide Bond No. 965002976
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.) 5028' Ungraded		22. APPROXIMATE DATE WORK WILL START: December 1, 2008	23. ESTIMATED DURATION: 25 DAYS

## 24. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
24"	20" - CORRUGATED CONDUCTOR	60'	40 CUBIC YARD CONSTRUCTION CEMENT
12-1/4"	9-5/8" 47#, N-80, LT&C	90'	SEE ATTACHED DRILLING PLAN
12-1/4"	9-5/8" 36#, J-55, LT&C	500'	SEE ATTACHED DRILLING PLAN
7-7/8"	4-1/2" 13.5#, P-110, LT&C	8,620' MD	SEE ATTACHED DRILLING PLAN

## 25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |   |  |
|---|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER                            | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN                                   |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER<br>49-2204 Ouray Brine | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) G. T. NIMMOTITLE OPERATIONS MANAGERSIGNATURE G. T. NimmoDATE 07/29/08

(This space for State use only)

API NUMBER ASSIGNED 49-047-40278

APPROVAL:


RECEIVED

JUL 31 2008

DIV. OF OIL, GAS &amp; MINING

# T10S, R19E, S.L.B.&M.

N89°53'E - 5318.28' (G.L.O.)



## BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

## LEGEND:

- └─ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.


NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°58'25.99" (39.973886)	LATITUDE = 39°58'12.43" (39.970119)
LONGITUDE = 109°45'12.73" (109.753536)	LONGITUDE = 109°45'10.29" (109.752858)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°58'26.12" (39.973922)	LATITUDE = 39°58'12.56" (39.970156)
LONGITUDE = 109°45'10.23" (109.752842)	LONGITUDE = 109°45'07.79" (109.752164)

## WEXPRO COMPANY

Well location, ISLAND UNIT #89, located as shown in the SE 1/4 SW 1/4 of Section 2, T10S, R19E, S.L.B.&M., Uintah County Utah.

## BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 20, T10S, R20E, S.L.B.&M., TAKEN FROM THE BIG PACK MTN. NW QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5251 FEET.



SCALE

## CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

**UINTAH ENGINEERING & LAND SURVEYING**  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 02-27-08	DATE DRAWN: 03-06-08
PARTY D.R. A.W. C.C.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE WEXPRO COMPANY	

**Drilling Plan  
Wexpro Company  
Island Unit Well No. 89  
Uintah County, Utah**

1. SURFACE FORMATION, ESTIMATED TOPS AND WATER, OIL, GAS OR MINERAL BEARING FORMATIONS:

Formation	Depth - MD	Depth - TVD	Remarks
<b>Uinta</b>	Surface	Surface	
<b>Green River</b>	1,945'	1,943'	
<b>Bird's Nest</b>	2,420'	2,400'	
<b>Wasatch Tongue</b>	4,750'	4,480'	
<b>Green River Tongue</b>	5,156'	4,865'	
<b>Wasatch</b>	5,314'	5,020'	Gas, Major Objective
<b>Lower Wasatch</b>	7,439'	7,145'	Gas, Major Objective
<b>Mesaverde</b>	8,520'	8,226'	
<b>Total Depth</b>	8,620'	8,326'	

All fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and adequately protected.

2. PRESSURE CONTROL EQUIPMENT: (See attached diagram) Operator's minimum specifications for pressure control equipment require an 11-inch 3000 psi double gate hydraulically operated blowout preventer and an 11-inch 3000 psi annular preventer. BOP equipment will be tested to its rated working pressure or 70-percent of the internal yield of the surface casing. The annular preventer will be tested at 50-percent of its rated working pressure.

NOTE: The surface casing will be pressure tested to a minimum of 1500 psi. BOP's will be checked daily as to mechanical operating condition and will be tested by rig equipment after each string of casing is run. All ram type preventers will have hand wheels which will be operative and accessible at the time the preventers are installed.

**AUXILIARY EQUIPMENT:**

- a. Manually operated kelly cock
- b. No floats at bit

- c. Monitoring of mud system will be with PVT system
- d. Full opening floor valves in the full open position, capable of fitting all drill stem connections manually operated
- e. Formation integrity test will be done 20' below surface casing shoe to 11.0 ppg

3. CASING PROGRAM:

Hole Size	Size	Top	Bottom	Weight	Grade	Thread	Condition
24"	20"	sfc	60'				Steel Conductor
12-1/4"	9-5/8"	sfc	90'	47	N80	LTC	New
12-1/4"	9-5/8"	90'	500'	36	J55	LTC	New
7-7/8"	4-1/2"	sfc	8,620' MD	13.5	P110	LTC	New

Casing Strengths:				Collapse	Burst	Tensile (minimum)
9-5/8"	47 lb.	N80	LTC	4,760 psi	6,870 psi	905,000 lb.
9-5/8"	36 lb.	J55	LTC	2,020 psi	3,520 psi	453,000 lb.
4-1/2"	13.5 lb.	P110	LTC	10,680 psi	12,410 psi	338,000 lb

CEMENTING PROGRAMS:

9-5/8-inch Surface Casing: 333 cu.ft. of Class G with 2% CaCl<sub>2</sub> (1/4% celloflake will only be used if lost circulation is encountered).

4-1/2-inch Production Casing:

**Lead:** 1378 cu. ft. Light cement with retarder, reducer and fluid loss additives, if needed.

**Tail:** 1100 cu. ft. Light cement with retarder, reducer, and fluid loss additives, if needed.

4. MUD PROGRAM:

Surface to 500 feet: Surface to be drilled with a dry hole rig.

Surface to TD: Fresh water with gels and polymer sweeps, as necessary from 500 feet to Total Depth. Mud up, mud weight of 9.0 - 10.0 ppg, and maintain this to total depth.

Sufficient mud materials to maintain mud properties, control lost circulation and to contain blowout will be available at the wellsite.

No chrome constituent additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. LOGGING: DIL-GR-SFL - Total Depth to surface casing  
MICRO-LOG - Total Depth to surface casing  
FDC/CNL/GR/CAL - Total Depth to surface casing  
BORE HOLE PROFILE LOG- Total Depth to surface casing

TESTING: None

CORING: None

6. ABNORMAL PRESSURE AND TEMPERATURE: No abnormal pressures are anticipated. A BHT of 157 degrees F.

7. ANTICIPATED STARTING DATE: December 1, 2008

DURATION OF OPERATION: 25 days

# ISLAND UNIT WELL NO. 89 - CEMENT DESIGN

## **SURFACE CASING:**

CASING:	9-5/8", 36#, K-55	0.4340 cu.ft./lin.ft	
ANNULUS:	12-1/4" (Guage Hole)	0.3132 cu.ft./lin.ft	
EXCESS:		100%	
CEMENT YIELD:	CLASS "G" NEAT	1.15 cu.ft./sack	15.2 ppg
	TAIL	1.15 cu.ft./sack	
TOTAL DEPTH		500 Feet	
TOP OF TAIL		0 Feet	(Surface)
TOP OF LEAD		0 Feet	(Surface)

### **LEAD SLURRY**

CU.FT

ANN	0 TO	0	0.3132	0.00		
ANN EXCESS			100%	0.00		
				0.00	0 SACKS	0 CU.FT.

### **TAIL SLURRY**

CU.FT

CSG	500 TO	455	0.4340	19.53		
ANN	500 TO	0	0.3132	156.6		
ANN EXCESS			100%	156.6		
				332.73	289 SACKS	333 CU.FT.
				DISPLACEMENT	35.2 BBLs	

## **PRODUCTION CASING:**

CASING:	4-1/2", 13.5#, P-110	0.0838 cu.ft./lin.ft	
ANNULUS:	8-1/8" (From Carbide Lag)	0.2496 cu.ft./lin.ft	
EXCESS:		15%	
CEMENT YIELD:	LEAD	2.83 cu.ft./sack	11.3 ppg
	TAIL	1.27 cu.ft./sack	15.2 ppg
TOTAL DEPTH		8,620 Feet	MD
TOP OF TAIL		4,800 Feet	(Top of Wasatch Tongue)
TOP OF LEAD		0 Feet	

### **LEAD SLURRY**

CU.FT

ANN	4800 TO	0	0.2496	1198.08		
ANN EXCESS			15%	179.71		
				1377.79	487 SACKS	1378 CU.FT.

### **TAIL SLURRY**


CU.FT

CSG	8,620 TO	8,575	0.0838	3.771		
ANN	8,620 TO	4,800	0.2496	953.472		
ANN EXCESS			15%	143.02		
				1100.26	866 SACKS	1100 CU.FT.
				DISPLACEMENT	128.0 BBLs	


Island Unit 89  
Approximate Directional Plan  
(S. L. Russell 6-18-2008)

Measured Depth	TVD	Inclination	Azimuth	N/S Offset	E/W offset	Closure
0	0.00	0	351	0.00	0.00	0.00
500	500.00	0	351	0.00	0.00	0.00
1000	1000.00	0	351	0.00	0.00	0.00
1500	1500.00	0	351	0.00	0.00	0.00
1600	1599.98	2	351	1.72	-0.27	1.74
1700	1699.84	4	351	6.89	-1.09	6.98
1800	1799.45	6	351	15.50	-2.46	15.69
1900	1898.70	8	351	27.54	-4.36	27.88
2000	1997.47	10	351	42.99	-6.81	43.53
2100	2095.45	13	351	62.68	-9.93	63.46
2200	2192.25	16	351	87.40	-13.84	88.49
2300	2287.61	19	351	117.10	-18.55	118.56
2400	2381.27	22	351	151.69	-24.02	153.58
2500	2472.96	25	351	191.06	-30.26	193.44
2600	2562.84	27	351	234.36	-37.12	237.28
2700	2651.94	27	351	279.20	-44.22	282.68
2800	2741.04	27	351	324.04	-51.32	328.08
2900	2830.14	27	351	368.88	-58.42	373.48
3000	2919.24	27	351	413.72	-65.53	418.88
4600	4344.85	27	351	1131.16	-179.16	1145.26
4700	4434.73	25	351	1174.46	-186.02	1189.10
4800	4526.08	23	351	1214.63	-192.38	1229.77
4900	4619.11	20	351	1250.82	-198.11	1266.41
5000	4713.93	17	351	1282.16	-203.07	1298.14
5100	4810.28	14	351	1308.55	-207.25	1324.86
5200	4907.90	11	351	1329.93	-210.64	1346.51
5300	5006.52	8	351	1346.23	-213.22	1363.01
5400	5105.86	5	351	1357.41	-214.99	1374.33
5500	5205.66	2	351	1363.43	-215.95	1380.43
5600	5305.64	0	351	1365.16	-216.22	1382.18
5700	5405.64	0	351	1365.16	-216.22	1382.18
5800	5505.64	0	351	1365.16	-216.22	1382.18
5900	5605.64	0	351	1365.16	-216.22	1382.18
6000	5705.64	0	351	1365.16	-216.22	1382.18
6100	5805.64	0	351	1365.16	-216.22	1382.18
8620	8326.00	0	351	1365.16	-216.22	1382.18


Island Unit 89 - Map View




Island Unit 89 - Side view looking North



Island Unit 89 - Oblique side view




# 3,000 psi BOP Minimum Requirements



3M CHOKES MANIFOLD EQUIPMENT — CONFIGURATION MAY VARY

46812 Federal Register / Vol. 53, No. 223 / Friday, November 18, 1988 / Rules and Regulations



**Surface Use and Operations**  
**Wexpro Company**  
**Island Unit Well No. 89**  
(Island Unit Well 17, 88, 89, 90, 91 Pad)  
**Uintah County, Utah**

1. Existing Road:
  - A. Proposed Well Site as Staked: Refer to well location plat and area map.
  - B. Proposed Access Route: Refer to general area map. All access roads are within lease boundaries.
  - C. Plans for Improvement and/or Maintenance: All existing roads utilized will be maintained in their present condition and no improvements will be made.
2. Planned Access Roads:
  - A. The existing road and approximately 960 feet of newly constructed road connecting the existing road to the drilling pad will necessitate a 30-foot wide right-of-way (maximum disturbance).
  - B. Maximum grade: Will not exceed 10 percent.
  - C. Turnouts: Water turnouts will be constructed as required to divert runoff water from the road ditch in such a manner as to not cause erosion.
  - D. Location (centerline): Access road has been staked and flagged. Surface disturbance and vehicular travel will be limited to the approved access route, additional area needed will be approved in advance.
  - E. One 18" CMP is required where the access road leaves the location.
  - F. Surface materials: Surface materials will be obtained from cuts along the access road and location. Spot surfacing may be required to maintain the running surface.
  - G. Any topsoil (approximately 6-inches) removed in conjunction with road construction will be spread in the borrow ditches or windrowed to the side. Borrow areas will be seeded as discussed in reclamation procedures.
3. Location of Existing Wells: Refer to area map for the location of existing wells within a one-mile radius.
4. Location of Existing and/or Proposed Facilities: Refer to area maps. Facilities will be installed as detailed on the attached diagram.

All above ground structures not subject to safety requirements will be painted to blend with the natural colors of the landscape. The color chosen is Covert Green. All facilities will be painted as weather permits, but no later than one year after well is turned on for initial production.

If a tank battery is constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain 110% of the largest storage tank.

All loading lines will be placed inside the berm surrounding the tank battery.

All site security guidelines identified in 43 CFR 3162.7 regulations will be adhered to.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from Authorized Officer.

#### Pipeline

Additional pipeline will not be required. All natural gas is to be transported via the current existing line serving Island Unit Well No. 17.

5. Location and Type of Water Supply: Water will be hauled by tank trucks from the Ouray Brine water well located in Section 9-T8S-R20E, Water Use Claim #43-10610.
6. Source of Construction Materials: All materials will be derived from cuts at the location and along the access road. Construction material will be located on lease.
7. Methods for Handling Water Disposal: Cuttings and drilling fluids will be placed in a lined mud pit which will be constructed with at least one half of its holding capacity below ground level. The mud pit will be fenced on three sides with a sheep-tight fence of woven wire prior to the onset of drilling. Immediately upon completion of drilling, the fourth side will be fenced and the liquids allowed to evaporate. The fence will be maintained until restoration. Any produced liquids will be contained in test tanks and hauled out by tank trucks. Garbage and other waste materials will be placed in a trash cage, the contents of which will be disposed of in the nearest legal landfill. Portable sewage facilities will be utilized for the disposal of human waste.

Produced waste water will be confined to a lined pit for a period not to exceed 90 days after initial production. Produced water will be confined to a 400 barrel tank on location and application is made at this time for approval of disposal of, the excess water produced, to be hauled to one of the following State of Utah approved disposal sites: RN Industries Inc, Sec 4-2S-2W, Bluebell; LaPoint Recycle & Storage, Sec 12-5S-19E, LaPoint; or to Dalbo, Inc, Sec 2-6S-20E, Vernal. All excess produced water will be hauled by tank truck over Unit, Tribal, County and State roads.

8. Ancillary Facilities: Camp facilities will not be required.

9. Wellsite Layout: Refer to drawing.
10. Plans for Restoration of the Surface: During construction, all woody vegetation and the top six-inches of topsoil material will be removed from the pad and stockpiled separately. All pits will remain fenced until cleanup begins. Overhead flagging will be installed if oil is in the mud pit.

Immediately upon completion of drilling, the location and surrounding area will be cleared of all debris, materials, trash and junk not required for production. The reserve pit and that portion of the location and access road not needed for production or production facilities will be reclaimed.

Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed. All disturbed areas will be re-contoured to the approximate natural contours to the satisfaction of the Authorized Officer.

The stockpiled topsoil will be evenly distributed over the disturbed areas. Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface. Reseeding will be done in the fall before ground frost.

A seed drill equipped with a regulator will be required. Seed will be drilled 1/4-1/2 inch deep on the contour using the following seed mixture specified by the Bureau of Land Management.

Species	lbs. PLS/acre
Shadscale	3 lbs PLS/acre
Gardner's Saltbush	3 lbs PLS/acre
Indian Rice Grass	3 lbs PLS/acre
Blue Bunchgrass	3 lbs PLS/acre

Where drilling is not possible a broadcast/rake method will be used doubling the seed mixture.

11. Surface and Mineral Ownership: Surface ownership along the access road is federal and surface ownership at the wellsite is federal.
12. Other Information: Anna Figueroa of the Bureau of Land Management, Vernal Field Office in Vernal, Utah will be notified at least 72-hours prior to commencement of both construction and reclamation operations.

A Class III Cultural Resource Inventory will be completed and the report forwarded to the Bureau of Land Management.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

13. Lessee's or Operators Representative and Certification:


G. T. Nimmo, Operations Manager, P. O. Box 458, Rock Springs, Wyoming 82902, telephone number (307) 382-9791.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions which currently exist, that the statements made in the plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Wexpro Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Please be advised that Wexpro Company is considered to be the operator of Well No. 89; SE ¼, SW ¼, Section 2, Township 10S Range 19E; Lease ML-11004, Uintah County; and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by BLM Bond ESB000024, Nationwide Bond No. 965002976

Date: 08/10/08

Name   
G. T. Nimmo, Operations Manager

**WEXPRO COMPANY**  
**ISLAND UNIT #88, 89, 90 & 91**  
**LOCATED IN UINTAH COUNTY, UTAH**  
**SECTION 2, T10S, R19E, S.L.B.&M.**




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKES

CAMERA ANGLE: EASTERLY




PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: EASTERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
 85 South 200 East Vernal, Utah 84078  
 435-789-1017 uels@uelsinc.com


LOCATION PHOTOS			02	29	08	PHOTO
			MONTH	DAY	YEAR	
TAKEN BY: D.R.	DRAWN BY: C.P.		REVISED: 00-00-00			

# WEXPRO COMPANY

## LOCATION LAYOUT FOR

ISLAND UNIT #88, #89, #90 & #91  
SECTION 2, T10S, R19E, S.L.B.&M.  
SE 1/4 SW 1/4

FIGURE #1




SCALE: 1" = 60'  
DATE: 03-06-08  
Drawn By: C.C.



**NOTE:**  
Flare Pit is to be located a min. of 100' from the Well Head.

**RESERVE PITS**  
Total Pit Capacity  
W/2' of Freeboard  
= 50,160 Bbls.±  
Total Pit Volume  
= 12,260 Cu. Yds



Elev. Ungraded Ground at I.U. #90 Location Stake = 5027.4'  
Elev. Graded Ground at Location Stake = 5024.4'


UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

1" = 40'  
X-Section  
Scale  
1" = 100'

DATE: 03-06-08  
Drawn By: C.C.

**WEXPRO COMPANY**  
**TYPICAL CROSS SECTIONS FOR**  
**ISLAND UNIT #88, #89, #90 & #91**  
**SECTION 2, T10S, R19E, S.L.B.&M.**  
**SE 1/4 SW 1/4**

**FIGURE #2**



\* NOTE:  
FILL QUANTITY INCLUDES  
5% FOR COMPACTION

NOTE:  
Topsoil should not be  
Stripped Below Finished  
Grade on Substructure Area.

**APPROXIMATE YARDAGES**


**APPROXIMATE ACREAGES**  
**WELL SITE DISTURBANCE = ±4.948 ACRES**  
**ACCESS ROAD DISTURBANCE = ±0.664 ACRES**  
**TOTAL = ±5.612 ACRES**

(6") Topsoil Stripping = 3,720 Cu. Yds.  
Remaining Location = 45,230 Cu. Yds.  
**TOTAL CUT = 48,950 CU.YDS.**  
**FILL = 10,460 CU.YDS.**


**EXCESS MATERIAL = 38,490 Cu. Yds.**  
**Topsoil & Pit Backfill = 9,850 Cu. Yds.**  
**(1/2 Pit Vol.)**  
**EXCESS UNBALANCE = 28,640 Cu. Yds.**  
**(After Interim Rehabilitation)**


**UINTAH ENGINEERING & LAND SURVEYING**  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

ISLAND UNIT #88, #89, #90 & #91  
SECTION 2, T10S, R19E, S.L.B.&M.  
SE 1/4 SW 1/4



SCALE: 1" = 60'  
DATE: 03-06-08  
Drawn By: C.C.





# LEGEND:

⊙ PROPOSED LOCATION

# WEXPRO COMPANY

ISLAND UNIT #88, 89, 90 & 91  
SECTION 2, T10S, R19E, S.L.B.&M.  
SE 1/4 SW 1/4



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813




TOPOGRAPHIC  
MAP

02 29 08  
MONTH DAY YEAR

SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00





# **LEGEND:**

————— EXISTING ROAD  
 - - - - - PROPOSED ACCESS ROAD



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813




## **WEXPRO COMPANY**

**ISLAND UNIT #88, 89, 90 & 91**  
**SECTION 2, T10S, R19E, S.L.B.&M.**  
**SE 1/4 SW 1/4**

**TOPOGRAPHIC** 02 29 08  
**MAP** MONTH DAY YEAR  
 SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00





# LEGEND:

- |                   |                         |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS  | ● WATER WELLS           |
| ● PRODUCING WELLS | ● ABANDONED WELLS       |
| ● SHUT IN WELLS   | ● TEMPORARILY ABANDONED |



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



# WEXPRO COMPANY


ISLAND UNIT #88, 89, 90 & 91  
 SECTION 2, T10S, R19E, S.L.B.&M.  
 SE 1/4 SW 1/4

TOPOGRAPHIC	02	29	08
MAP	MONTH	DAY	YEAR
SCALE: 1" = 2000'	DRAWN BY: C.P.		REVISED: 00-00-00



**FIGURE #1**

A wind rose diagram with a central circle labeled 'N'. Four arrows radiate from the center: one pointing North, one pointing North-East, one pointing South-East, and one pointing South. The North arrow is the longest, followed by the North-East arrow. The words 'Prevailing' and 'Winds' are written on the left and right sides of the diagram respectively.



Elev. Ungraded Ground at I.U. #90 Location Stake = 5027.4'  
Elev. Graded Ground at Location Stake = 5024.4'

**UINTAH ENGINEERING & LAND SURVEYING**  
 85 E. 900 Road • Kemmerer, Utah 84092 • (435) 882-4007

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB NO. 1004-0137  
Expires: July 31, 2010

5. Lease Serial No.

ML 11004

6. If Indian, Allottee or Tribe Name

n/a

7. If Unit or CA Agreement, Name and No.

ISLAND UNIT UTU063026X

8. Lease Name and Well No.

ISLAND UNIT NO. 89

9. API Well No.

PENDING

10. Field and Pool, or Exploratory

ISLAND, WASATCH

11. Sec., T., R., M., or Blk. and Survey or Area

2 T 10S R 19E S.L.B.  
&M.

12. County or Parish

UINTAH

13. State

UTAH

1a. Type of Work: ☒ DRILL

☐ REENTER

1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

WEXPRO COMPANY

3a. Address

P.O. BOX 458, ROCK SPRINGS, WY 82902

3b. Phone No. (include area code)

307 382-9791

4. Location of well (Report location clearly and in accordance with any State requirements. \*)

At surface 297' FSL 1940' FWL SE SW Lat. 39.970119 Long. 109.752858

At proposed prod. zone 1670' FSL 1770' FWL NE SW

14. Distance in miles and direction from the nearest town or post office\*

APPROXIMATELY 32 MILES FROM VERNAL, UTAH

15. Distance from proposed\*

location to nearest  
property or lease line, ft. 1670'  
(Also to nearest drlg. unit line, if any)

16. No. of acres in lease

645.79

17. Spacing Unit dedicated to this well

N/A

18. Distance from proposed location\*

to nearest well, drilling, completed, 1500'  
applied for, on this lease, ft.

19. Proposed Depth

8620' (MD) 8326' (TVD)

20. BLM/ BIA Bond No. on file

Nationwide Bond No. 965002976

21. Elevations (Show whether DF, RT, GR, etc.)

5028' Ungraded

22. Approximate date work will start\*

December 1, 2008

23. Estimated duration

25 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1 shall be attached to this form:

1. Well plat certified by a registered surveyor.

2. A Drilling Plan.


3. A Surface Use Plan (if the location is on National Forest System Land  
SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by existing bond on file (see  
item 20 above).

5. Operator certification.

6. Such other site specific information and/ or plans as may be required by  
authorized officer. *WTD*

25. Signature



Name (Printed/ Typed)

G. T. NIMMO

Date

05/10/08

Title

OPERATIONS MANAGER

Approved By (Signature)

Name (Printed/ Typed)

Date

Title

Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to  
conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United  
States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 07/31/2008

API NO. ASSIGNED: 43-047-40278

WELL NAME: ISLAND U 89

OPERATOR: WEXPRO COMPANY ( N1070 )

PHONE NUMBER: 307-382-9791

CONTACT: G.T. NIMMO

PROPOSED LOCATION:

SESW 02 100S 190E

SURFACE: 0297 FSL 1940 FWL

BOTTOM: 1670 FSL 1770 FWL

COUNTY: UINTAH

LATITUDE: 39.97010 LONGITUDE: -109.7520

UTM SURF EASTINGS: 606579 NORTHINGS: 4424975

FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /

**Tech Review**

**Initials**

**Date**

Engineering

*DND*

*9/11/08*

Geology

Surface

LEASE TYPE: 3 - State

LEASE NUMBER: ML 11004

SURFACE OWNER: 3 - ~~State~~ *Federal*

PROPOSED FORMATION: WSTC

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. 965003033 )

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit

(No. 49-2204 )

☒ RDCC Review (Y/N)

(Date: \_\_\_\_\_ )

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

       R649-2-3.

Unit: ISLAND

       R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

       R649-3-3. Exception

       Drilling Unit

Board Cause No: \_\_\_\_\_

Eff Date: \_\_\_\_\_

Siting: \_\_\_\_\_

☒ R649-3-11. Directional Drill

COMMENTS: \_\_\_\_\_

STIPULATIONS: \_\_\_\_\_

*1- Spacing Shp*

*2- STATEMENT OF BASIS*

PREPARED BY: DIANA MASON  
DATE: 4-AUGUST-2008

# Application for Permit to Drill

## Statement of Basis

9/11/2008

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Ownr</b>	<b>CBM</b>
913	43-047-40278-00-00		GW	S	No
<b>Operator</b>	WEXPRO COMPANY	<b>Surface Owner-APD</b>			
<b>Well Name</b>	ISLAND U 89	<b>Unit</b>	ISLAND		
<b>Field</b>	NATURAL BUTTES	<b>Type of Work</b>			
<b>Location</b>	SESW 2 10S 19E S 297 FSL 1940 FWL	GPS Coord (UTM)	606579E 4424975N		

### Geologic Statement of Basis

Wexpro proposes to set 590 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at 3,000 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 2. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The proposed surface casing and cement should adequately protect any near surface aquifers. The production string cement should be brought up above the base of the moderately saline water to prevent it from mixing with fresher waters up hole.

Brad Hill  
APD Evaluator

9/11/2008  
Date / Time

### Surface Statement of Basis

The surface rights at the proposed location are owned by the Federal Government. The operator is responsible for obtaining all required surface permits and rights-of-way from the BLM.

Brad Hill  
Onsite Evaluator


9/11/2008  
Date / Time

### Conditions of Approval / Application for Permit to Drill

<b>Category</b>	<b>Condition</b>
	None

# 43047402780000 Island U 89

## Casing Schematic



Well name:	<b>43047402780000 Island U 89</b>		
Operator:	<b>Wexpro Company</b>		
String type:	<b>Surface</b>	Project ID:	<b>43-047-40278-0000</b>
Location:	<b>Uintah County</b>		

**Design parameters:**

**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 73 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 185 ft

Cement top: 66 ft

**Burst**

Max anticipated surface pressure: 519 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 590 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 513 ft

**Non-directional string.**

**Re subsequent strings:**

Next setting depth: 8,326 ft  
Next mud weight: 10.000 ppg  
Next setting BHP: 4,325 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 590 ft  
Injection pressure: 590 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
2	100	9.625	47.00	N-80	LT&C	100	100	8.625	41.1
1	490	9.625	36.00	J-55	LT&C	590	590	8.796	212.7

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
2	44	4738	99.990	531	6870	12.93	22	905	40.51 J
1	257	2020	7.846	590	3520	5.97	18	453	25.68 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 810-538-5357

Date: August 26, 2008  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 590 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>43047402780000 Island U 89</b>		
Operator:	<b>Wexpro Company</b>		Project ID:
String type:	Production		43-047-40278-0000
Location:	Uintah County		

**Design parameters:**

**Collapse**

Mud weight: 10.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 65 °F  
Bottom hole temperature: 182 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 724 ft

**Burst**

Max anticipated surface pressure: 2,494 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 4,325 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

**Directional Info - Build & Drop**

Kick-off point 1000 ft  
Departure at shoe: 1385 ft  
Maximum dogleg: 2.8 °/100ft  
Inclination at shoe: 0 °

Tension is based on air weight.  
Neutral point: 7,391 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	8620	4.5	13.50	P-110	LT&C	8326	8620	3.795	722.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	4325	10680	2.469	4325	12410	2.87	112	338	3.01 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 810-538-5357

Date: August 26, 2008  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 8326 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

*Engineering responsibility for use of this design will be that of the purchaser.*

# BOPE REVIEW

Wexpro Island Unit 89

43-047-40278-0000

## INPUT

Well Name

Casing Size (")

Setting Depth (TVD)

Previous Shoe Setting Depth (TVD)

Max Mud Weight (ppg)

BOPE Proposed (psi)

Casing Internal Yield (psi)

Operators Max Anticipated Pressure (psi)

Wexpro Island Unit 89 43-047-40278-0000	
String 1	String 2
9 5/8	4 1/2
590	8326
60	590
8.4	10
0	3000
3520	12410
3580	8.3 ppg

## Calculations

String 1 9 5/8 "	
Max BHP [psi]	.052*Setting Depth*MW = 258
BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) = 187 NO Drilled dry
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) = 128 NO Known Area ok.
*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) = 141 NO ok.
Required Casing/BOPE Test Pressure	590 psi
*Max Pressure Allowed @ Previous Casing Shoe =	60 psi
*Assumes 1psi/ft frac gradient	

## Calculations

String 2 4 1/2 "	
Max BHP [psi]	.052*Setting Depth*MW = 4330
BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) [psi]	Max BHP-(0.12*Setting Depth) = 3330 NO
MASP (Gas/Mud) [psi]	Max BHP-(0.22*Setting Depth) = 2498 YES
*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth) = 2628 NO Known Area - Common in Area ok
Required Casing/BOPE Test Pressure	3000 psi
*Max Pressure Allowed @ Previous Casing Shoe =	590 psi
*Assumes 1psi/ft frac gradient	

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:  
3160  
(UT-922)

August 4, 2008

### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2008 Plan of Development Island Unit, Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2008 within the Island Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
Proposed PZ Wasatch/MesaVerde)		
43-047-40277	Island U 90 Sec 02 T10S R19E 0317 FSL 1939 FWL	BHL Sec 02 T10S R19E 0750 FSL 2090 FEL
43-047-40279	Island U 95 Sec 12 T10S R19E 1094 FSL 1631 FWL	BHL Sec 12 T10S R19E 2520 FNL 2160 FWL
43-047-40281	Island U 87 Sec 12 T10S R19E 1084 FSL 1648 FWL	BHL Sec 12 T10S R19E 0560 FSL 1675 FWL
(Proposed PZ Wasatch)		
43-047-40280	Island U 91 Sec 02 T10S R19E 0257 FSL 1942 FWL	BHL Sec 11 T10S R19E 0170 FNL 1830 FWL
43-047-40276	Island U 88 Sec 02 T10S R19E 0277 FSL 1941 FWL	BHL Sec 02 T10S R19E 1110 FSL 0530 FWL
43-047-40278	Island U 89 Sec 02 T10S R19E 0297 FSL 1940 FWL	BHL Sec 02 T10S R19E 1670 FSL 1770 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

DEPARTMENT OF NATURAL RESOURCES  
DEPARTMENT OF OIL, GAS AND MININGAMENDED REPORT ☒  
(highlight changes)

## APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: ML 11004	6. SURFACE: FEDERAL
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
2. NAME OF OPERATOR: WEXPRO COMPANY		8. UNIT or CA AGREEMENT NAME: ISLAND UTU063026X	
3. ADDRESS OF OPERATOR: P.O. BOX 458 CITY ROCK SPRINGS STATE WY ZIP 82902		PHONE NUMBER: 307 382-9791	9. NAME OF WELL and NUMBER ISLAND UNIT WELL NO. 89
4. LOCATION OF WELLS (FOOTAGES) AT SURFACE: 297' FSL, 1940' FWL AT PRODUCING ZONE: 1670' FSL, 1770' FWL		10. FIELD AND POOL, OR WILDCAT: ISLAND, WASATCH	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: APPROXIMATELY 32 MILES FROM VERNAL, UTAH		12. COUNTY UINTAH	13. STATE UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1670' (BHL)	16. NUMBER OF ACRES IN LEASE: 645.79	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: N/A	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1400'	19. PROPOSED DEPTH: 8,620' (MD) 8,326' (TVD)	20. BOND DESCRIPTION: Nationwide Bond No. 965002976	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.) 5028' Ungraded	22. APPROXIMATE DATE WORK WILL START: December 1, 2008	23. ESTIMATED DURATION: 25 DAYS	

## 24. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
24"	20" - CORRUGATED CONDUCTOR	60'	40 CUBIC YARD CONSTRUCTION CEMENT
12-1/4"	9-5/8" 47#, N-80, LT&C	90'	SEE ATTACHED DRILLING PLAN
12-1/4"	9-5/8" 36#, J-55, LT&C	500'	SEE ATTACHED DRILLING PLAN
7-7/8"	4-1/2" 13.5#, P-110, LT&C	8,620' MD	SEE ATTACHED DRILLING PLAN

## 25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- |   |  |
|---|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER                            | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN                                   |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER<br>49-2204 Ouray Brine | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) G. T. NIMMO

TITLE OPERATIONS MANAGER

SIGNATURE

DATE

(This space for State use only)

API NUMBER ASSIGNED

43-047-40278

Approved by the  
Utah Division of  
Oil, Gas and Mining

RECEIVED

AUG 13 2008

DIV. OF OIL, GAS &amp; MINING

Date:

08-11-08

By:

[Signature]



Wexpro Company

180 East 100 South

P.O. Box 45601

Salt Lake City, UT 84145-0601

Tel 801 324 2600 • Fax 801 324 2637

August 14, 2008

Ms. Diane Mason  
State of Utah  
Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114-5801

43-047 40278

Re: Request for Exception Location and for Approval of Directional Drilling  
Island Unit #89 Well  
SURFACE: 297' FSL, 1940' FWL, SE $\frac{1}{4}$ SW $\frac{1}{4}$ , Sec. 2, T10S, R19E, SLM  
BOTTOM HOLE: 1670' FSL, 1770' FWL, NE $\frac{1}{4}$ SW $\frac{1}{4}$ , Sec. 2, T10S, R19E, SLM  
Lease No. U-4481

Dear Ms. Whitney:


In accordance with R649-3-3, Wexpro Company ("Wexpro") respectfully requests administrative approval for an exception location and for directional drilling of the Island Unit Well #89. As reflected on the plats included with the attached Application for Permit to Drill ("APD"), the captioned well is to be drilled directionally with a surface location in the SE $\frac{1}{4}$ SW $\frac{1}{4}$  and a proposed bottom hole location 1770' FWL and 1670' FSL in the NE $\frac{1}{4}$ SW $\frac{1}{4}$  of Section 2. All of Section 2 is committed to the Island Unit which is a Federal Exploratory Unit with Wexpro currently serving as the Unit Operator for the Unit.

Wexpro is permitting this well as a directional well due to topographic reasons. The surface location is from a shared well pad with the directional drilling required to reach the targeted bottom hole location. Pursuant to R649-3-11, Wexpro requests approval to drill the above-referenced well directionally. Ownership within 460' of the entire length of the proposed wellbore is owned 100% by Wexpro and its affiliate Questar Exploration and Production Company, thereby not requiring the approval of other parties for our intended operation.

We respectfully request the Division of Oil, Gas and Mining approve the APD as described in this letter. Should you have any questions, please call me at 801-324-5938.

Sincerely,

Wexpro Company

By:   
Jonathan M. Duke  
Coordinator: Contracts and Land

cc: Bureau of Land Management  
Dee Findlay – Wexpro Company  
Frank Nielsen – Questar Exploration and Production Company

RECEIVED

AUG 19 2008

**DRAFT**

FORM APPROVED  
OMB NO. 1004-0137  
Expires: July 31, 2010

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT


**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No.  ML 11004
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name  n/a
2. Name of Operator  WEXPRO COMPANY		7. If Unit or CA Agreement, Name and No. ISLAND UNIT UTU063026X
3a. Address P.O. BOX 458, ROCK SPRINGS, WY 82902		8. Lease Name and Well No. ISLAND UNIT NO. 89
3b. Phone No. (include area code) 307 382-9791		9. API Well No.  PENDING
4. Location of well (Report location clearly and in accordance with any State requirements. *) At surface 297' FSL 1940' FWL SE SW Lat. 39.970119 Long. 109.752858 At proposed prod. zone 1670' FSL 1770' FWL NE SW		10. Field and Pool, or Exploratory  ISLAND, WASATCH
11. Sec., T., R., M., or Blk. and Survey or Area  2 T 10S R 19E S.L.B. & M.		12. County or Parish UINTAH
13. State UTAH		14. Distance in miles and direction from the nearest town or post office* APPROXIMATELY 32 MILES FROM VERNAL, UTAH
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drlg. unit line, if any) 1670'	16. No. of acres in lease 645.79	17. Spacing Unit dedicated to this well N/A
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1500'	19. Proposed Depth 8620' (MD) 8326' (TVD)	20. BLM/ BIA Bond No. on file Nationwide Bond No. 965002976
21. Elevations (Show whether DF, RT, GR, etc.) 5028' Ungraded	22. Approximate date work will start* December 1, 2008	23. Estimated duration 25 days

**24. Attachments**

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1 shall be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by existing bond on file (see item 20 above).    |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Land, SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/ or plans as may be required by authorized officer. |

25. Signature 	Name (Printed/ Typed) G. T. NIMMO	Date 08/10/08
Title OPERATIONS MANAGER		
Approved By (Signature)	Name (Printed/ Typed)	Date
Title	Office	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

**RECEIVED**

\*(Instructions on page 2)

**AUG 19 2008**

DIV. OF OIL, GAS & MINING

FedEx 8/12/08

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DEPARTMENT OF OIL, GAS AND MINING

FORM 3

DRAFT

AMENDED REPORT ☒  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>		5. MINERAL LEASE NO: <b>ML 11004</b>	6. SURFACE: <b>FEDERAL</b>
1A. TYPE OF WORK DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: <b>ISLAND UTU063026X</b>	
2. NAME OF OPERATOR: <b>WEXPRO COMPANY</b>		9. NAME OF WELL and NUMBER <b>ISLAND UNIT WELL NO. 89</b>	
3. ADDRESS OF OPERATOR: <b>P.O. BOX 458 CITY ROCK SPRINGS STATE WY ZIP 82902</b>		10. FIELD AND POOL, OR WILDCAT: <b>ISLAND, WASATCH</b>	
4. LOCATION OF WELLS (FOOTAGES) AT SURFACE: <b>297' FSL, 1940' FWL</b> AT PRODUCING ZONE: <b>1670' FSL, 1770' FWL</b>		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>SE SW 2-10S-19E, SLB&amp;M</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>APPROXIMATELY 32 MILES FROM VERNAL, UTAH</b>		12. COUNTY <b>UINTAH</b>	13. STATE <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>1670' (BHL)</b>	16. NUMBER OF ACRES IN LEASE: <b>645.79</b>	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>N/A</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>1400'</b>	19. PROPOSED DEPTH: <b>8,620' (MD) 8,326' (TVD)</b>	20. BOND DESCRIPTION: <b>Nationwide Bond No. 965002976</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.) <b>5028' Ungraded</b>	22. APPROXIMATE DATE WORK WILL START: <b>December 1, 2008</b>	23. ESTIMATED DURATION: <b>25 DAYS</b>	


24. PROPOSED CASING AND CEMENTING PROGRAM			
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
24"	20" - CORRUGATED CONDUCTOR	60'	40 CUBIC YARD CONSTRUCTION CEMENT
12-1/4"	9-5/8" 47#, N-80, LT&C	90'	SEE ATTACHED DRILLING PLAN
12-1/4"	9-5/8" 36#, J-55, LT&C	500'	SEE ATTACHED DRILLING PLAN
7-7/8"	4-1/2" 13.5#, P-110, LT&C	8,620' MD	SEE ATTACHED DRILLING PLAN

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER <b>49-2204 Ouray Brine</b>	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) G. T. NIMMO TITLE OPERATIONS MANAGER


SIGNATURE  DATE \_\_\_\_\_

(This space for State use only)

API NUMBER ASSIGNED \_\_\_\_\_ APPROVAL: \_\_\_\_\_

T10S, R19E, S.L.B.&M.

N89°53'E - 5318.28' (G.L.O.)



#### BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

#### LEGEND:

- └ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- SECTION CORNERS LOCATED.


NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°58'25.99" (39.973886)	LATITUDE = 39°58'12.43" (39.970119)
LONGITUDE = 109°45'12.73" (109.753536)	LONGITUDE = 109°45'10.29" (109.752858)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°58'26.12" (39.973922)	LATITUDE = 39°58'12.56" (39.970158)
LONGITUDE = 109°45'10.23" (109.752842)	LONGITUDE = 109°45'07.79" (109.752164)

#### WEXPRO COMPANY

Well location, ISLAND UNIT #89, located as shown in the SE 1/4 SW 1/4 of Section 2, T10S, R19E, S.L.B.&M., Uintah County Utah.


#### BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 20, T10S, R20E, S.L.B.&M., TAKEN FROM THE BIG PACK MTN. NW QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5251 FEET.



#### CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**UINTAH ENGINEERING & LAND SURVEYING**  
**85 SOUTH 200 EAST - VERNAL, UTAH 84078**  
**(435) 789-1017**

SCALE 1" = 1000'	DATE SURVEYED: 02-27-08	DATE DRAWN: 03-06-08
PARTY D.R. A.W. C.C.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE WEXPRO COMPANY	



**Wexpro Company**

180 East 100 South

P.O. Box 45601

Salt Lake City, UT 84145-0601

Tel 801 324 2600 • Fax 801 324 2637

August 14, 2008

Ms. Diane Mason  
State of Utah  
Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114-5801

Re: Request for Exception Location and for Approval of Directional Drilling  
Island Unit #89 Well  
SURFACE: 297' FSL, 1940' FWL, SE $\frac{1}{4}$ SW $\frac{1}{4}$ , Sec. 2, T10S, R19E, SLM  
BOTTOM HOLE: 1670' FSL, 1770' FWL, NE $\frac{1}{4}$ SW $\frac{1}{4}$ , Sec. 2, T10S, R19E, SLM  
Lease No. U-4481

Dear Ms. Whitney:

In accordance with R649-3-3, Wexpro Company ("Wexpro") respectfully requests administrative approval for an exception location and for directional drilling of the Island Unit Well #89. As reflected on the plats included with the attached Application for Permit to Drill ("APD"), the captioned well is to be drilled directionally with a surface location in the SE $\frac{1}{4}$ SW $\frac{1}{4}$  and a proposed bottom hole location 1770' FWL and 1670' FSL in the NE $\frac{1}{4}$ SW $\frac{1}{4}$  of Section 2. All of Section 2 is committed to the Island Unit which is a Federal Exploratory Unit with Wexpro currently serving as the Unit Operator for the Unit.

Wexpro is permitting this well as a directional well due to topographic reasons. The surface location is from a shared well pad with the directional drilling required to reach the targeted bottom hole location. Pursuant to R649-3-11, Wexpro requests approval to drill the above-referenced well directionally. Ownership within 460' of the entire length of the proposed wellbore is owned 100% by Wexpro and its affiliate Questar Exploration and Production Company, thereby not requiring the approval of other parties for our intended operation.

We respectfully request the Division of Oil, Gas and Mining approve the APD as described in this letter. Should you have any questions, please call me at 801-324-5938.

Sincerely,

Wexpro Company

By: 

Jonathan M. Duke

Coordinator: Contracts and Land

cc: Bureau of Land Management  
Dee Findlay – Wexpro Company  
Frank Nielsen – Questar Exploration and Production Company

**DRAFT**

FORM APPROVED  
OMB NO. 1004-0137  
Expires: July 31, 2010

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

5. Lease Serial No.

ML 11004

6. If Indian, Allottee or Tribe Name  
n/a

7. If Unit or CA Agreement, Name and No.  
ISLAND UNIT UTU063026X

8. Lease Name and Well No.  
ISLAND UNIT NO. 89

9. API Well No.  
PENDING

10. Field and Pool, or Exploratory  
ISLAND, WASATCH

11. Sec., T., R., M., or Blk. and Survey or Area  
2 T 10S R 19E S.L.B. & M.

12. County or Parish  
UINTAH

13. State  
UTAH

1a. Type of Work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

WEXPRO COMPANY

3a. Address  
P.O. BOX 458, ROCK SPRINGS, WY 82902

3b. Phone No. (include area code)  
307 382-9791

4. Location of well (Report location clearly and in accordance with any State requirements. \*)  
At surface 297' FSL 1940' FWL SE SW Lat. 39.970119 Long. 109.752858  
At proposed prod. zone 1670' FSL 1770' FWL NE SW

14. Distance in miles and direction from the nearest town or post office\*  
APPROXIMATELY 32 MILES FROM VERNAL, UTAH

15. Distance from proposed\*  
location to nearest  
property or lease line, ft. 1670'  
(Also to nearest drlg. unit line, if any)

16. No. of acres in lease  
645.79

17. Spacing Unit dedicated to this well.  
N/A

18. Distance from proposed location\*  
to nearest well, drilling, completed,  
applied for, on this lease, ft. 1500'

19. Proposed Depth  
8620' (MD) 8326' (TVD)

20. BLM/ BIA Bond No. on file  
Nationwide Bond No. 965002976

21. Elevations (Show whether DF, RT, GR, etc.)  
5028' Ungraded

22. Approximate date work will start\*  
December 1, 2008

23. Estimated duration  
25 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1 shall be attached to this form:

1. Well plat certified by a registered surveyor.

2. A Drilling Plan.

3. A Surface Use Plan (if the location is on National Forest System Land SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by existing bond on file (see item 20 above).

5. Operator certification.

6. Such other site specific information and/ or plans as may be required by authorized officer.

25. Signature

Name (Printed/ Typed)

Date

Title

G. T. NIMMO

08/11/08

**OPERATIONS MANAGER**

Approved By (Signature)

Name (Printed/ Typed)

Date

Title

Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

FedEx 8/12/08

## STATE OF UTAH

FORM 3

DEPARTMENT OF NATURAL RESOURCES  
DEPARTMENT OF OIL, GAS AND MINING**DRAFT**AMENDED REPORT ☒  
(highlight changes)

## APPLICATION FOR PERMIT TO DRILL

1A. TYPE OF WORK DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		5. MINERAL LEASE NO: ML 11004	6. SURFACE: FEDERAL
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
2. NAME OF OPERATOR: <b>WEXPRO COMPANY</b>		8. UNIT or CA AGREEMENT NAME: ISLAND UTU063026X	
3. ADDRESS OF OPERATOR: P.O. BOX 458 CITY ROCK SPRINGS STATE WY ZIP 82902		PHONE NUMBER: 307 382-9791	9. NAME OF WELL and NUMBER ISLAND UNIT WELL NO. 89
4. LOCATION OF WELLS (FOOTAGES) AT SURFACE: 297' FSL, 1940' FWL AT PRODUCING ZONE: 1670' FSL, 1770' FWL		10. FIELD AND POOL, OR WILDCAT: ISLAND, WASATCH	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: APPROXIMATELY 32 MILES FROM VERNAL, UTAH		12. COUNTY UINTAH	13. STATE UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1670' (BHL)	16. NUMBER OF ACRES IN LEASE: 645.79	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: N/A	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1400'	19. PROPOSED DEPTH: 8,620' (MD) 8,326' (TVD)	20. BOND DESCRIPTION: Nationwide Bond No. 965002976	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.) 5028' Ungraded	22. APPROXIMATE DATE WORK WILL START: December 1, 2008	23. ESTIMATED DURATION: 25 DAYS	

## 24. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
24"	20" - CORRUGATED CONDUCTOR	60'	40 CUBIC YARD CONSTRUCTION CEMENT
12-1/4"	9-5/8" 47#, N-80, LT&C	90'	SEE ATTACHED DRILLING PLAN
12-1/4"	9-5/8" 36#, J-55, LT&C	500'	SEE ATTACHED DRILLING PLAN
7-7/8"	4-1/2" 13.5#, P-110, LT&C	8,620' MD	SEE ATTACHED DRILLING PLAN

## 25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER 49-2204 Ouray Brine	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) G. T. NIMMOTITLE OPERATIONS MANAGERSIGNATURE G. T. Nimmo

DATE \_\_\_\_\_


(This space for State use only)

API NUMBER ASSIGNED \_\_\_\_\_

APPROVAL: \_\_\_\_\_

**T10S, R19E, S.L.B.&M.**

N89°53'E - 5318.28' (G.L.O.)



**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

**LEGEND:**

└ = 90° SYMBOL

● = PROPOSED WELL HEAD.

SECTION CORNERS LOCATED.


NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°58'25.99" (39.973886)	LATITUDE = 39°58'12.43" (39.970119)
LONGITUDE = 109°45'12.73" (109.753536)	LONGITUDE = 109°45'10.29" (109.752858)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°58'26.12" (39.973922)	LATITUDE = 39°58'12.56" (39.970156)
LONGITUDE = 109°45'10.23" (109.752842)	LONGITUDE = 109°45'07.79" (109.752164)

**WEXPRO COMPANY**

Well location, ISLAND UNIT #89, located as shown in the SE 1/4 SW 1/4 of Section 2, T10S, R19E, S.L.B.&M., Uintah County Utah.


**BASIS OF ELEVATION**

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 20, T10S, R20E, S.L.B.&M., TAKEN FROM THE BIG PACK MTN. NW QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5251 FEET.



**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



**UINTAH ENGINEERING & LAND SURVEYING**  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 02-27-08	DATE DRAWN: 03-06-08
PARTY D.R. A.W. C.C.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE WEXPRO COMPANY	



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

September 11, 2008

Wexpro Company  
P O Box 458  
Rock Springs, WY 82902

Re: Island Unit Well No. 89 Well, 297' FSL, 1940' FWL, SE SW, Sec. 2, T. 10 South,  
R. 19 East, Bottom Location 1670' FSL, 1770' FWL, NE SW, Sec. 2, T. 10 South,  
R. 19 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-40278.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
Bureau of Land Management, Vernal Office  
SITLA



Operator: Wexpro Company  
Well Name & Number Island Unit Well No. 89  
API Number: 43-047-40278  
Lease: ML 11004

Location: SE SW Sec. 2 T. 10 South R. 19 East  
Bottom Location: NE SW Sec. 2 T. 10 South R. 19 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office (801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.
7. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML 11004
2. NAME OF OPERATOR: Wexpro Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: P.O. Box 458 CITY Rock Springs STATE WY ZIP 82902		7. UNIT or CA AGREEMENT NAME: UTU063026X
4. LOCATION OF WELL FOOTAGES AT SURFACE: 297' FSL, 1940' FWL		8. WELL NAME and NUMBER: Island Unit 89
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 2 10S 19E		9. API NUMBER: 4304740278
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Wasatch
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Air Rig Variance
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Wexpro Company requests a variance from 43 CFR 3160 Onshore Oil and Gas Order #2, Section III requirements, subsection E - Special Drilling Operations for the specific operation of drill and setting surface casing with a truck mounted air rig.

The Variance to Onshore #2 is requested because surface casing depth for this well is 500' and high pressure is not expected. A properly lubricated and maintained rotating head: A diverter bowl will be utilized in place of a rotating head. The diverter bowl will force the air and cutting returns to the reserve pit as it is used to drill the surface casing.

Blooie line discharge will be 100 feet from the well bore and securely anchored: The blooie line discharge for this operation will be located 50 to 70 feet from the wellhead.

Automatic ignitor or continuous pilot light on the blooie line: A diffuser will be used rather than an automatic pilot/ignitor. Water is injected into the compressed air and eliminates the need for the pilot light and the need for dust suppression equipment.

Compressor located in the direction from the blooie line is a minimum of 100' from the wellbore: Truck mounted air compressors will be located within 50 feet on the opposite side of the wellhead from the blooie line and equipped with a (1) emergency kill switch on the driller's console, (2) pressure relief valve on the compressor and (3) spark arrestors on the motors.

NAME (PLEASE PRINT) <u>G. T. Nimmo</u>	TITLE <u>Operations Manager</u>
SIGNATURE <u>[Signature]</u>	DATE <u>5/4/2009</u>

(This space for State use only)


COPY SENT TO OPERATOR

Date: 10.3.2009

(5/2000) Initials: KS

APPROVED BY THE STATE  
OF UTAH DIVISION OF  
OIL, GAS, AND MINING  
DATE: 5/19/09  
BY: [Signature] (See Instructions on Reverse Side)

RECEIVED  
MAY 07 2009  
DIV. OF OIL, GAS & MINING

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML 11004			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>  			
<b>2. NAME OF OPERATOR:</b> WEXPRO COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> ISLAND			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 458 , Rock Springs, WY, 82902		<b>8. WELL NAME and NUMBER:</b> ISLAND U 89			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0297 FSL 1940 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESW Section: 02 Township: 10.0S Range: 19.0E Meridian: S		<b>9. API NUMBER:</b> 43047402780000			
<b>PHONE NUMBER:</b> 307 922-5612 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>  <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 9/10/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<b>TYPE OF ACTION</b>  <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input checked="" type="checkbox"/> APD EXTENSION          OTHER: _____       </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: _____			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> The Island Unit #89 APD was originally approved on 9/11/2008 for a period of one year. Wexpro Company requests a renewal of the APD for an additional one year.					
<b>Approved by the Utah Division of Oil, Gas and Mining</b>  <b>Date:</b> <u>September 03, 2009</u> <b>By:</b> 					
<b>NAME (PLEASE PRINT)</b> Paul Jibson		<b>PHONE NUMBER</b> 307 922-5647			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Associate Permit Agent			
<b>DATE</b> 9/3/2009					



## The Utah Division of Oil, Gas, and Mining

- State of Utah  
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

### Request for Permit Extension Validation Well Number 43047402780000

**API:** 43047402780000

**Well Name:** ISLAND U 89

**Location:** 0297 FSL 1940 FWL QTR SESW SEC 02 TWP 100S RNG 190E MER S

**Company Permit Issued to:** WEXPRO COMPANY

**Date Original Permit Issued:** 9/11/2008

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Signature:** Paul Jibson

**Date:** 9/3/2009

**Title:** Associate Permit Agent **Representing:** WEXPRO COMPANY

**Date:** September 03, 2009

**By:** 

**RECEIVED** September 03, 2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML 11004
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> WEXPRO COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> ISLAND
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 458 , Rock Springs, WY, 82902		<b>8. WELL NAME and NUMBER:</b> ISLAND U 89
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0297 FSL 1940 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SESW Section: 02 Township: 10.0S Range: 19.0E Meridian: S		<b>9. API NUMBER:</b> 43047402780000
<b>PHONE NUMBER:</b> 307 922-5612 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 9/1/2010  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> <b>APD EXTENSION</b> OTHER: <span style="border: 1px solid black; display: inline-block; width: 100px; height: 15px;"></span>

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.**  

The Island Unit #89 APD was originally approved on 9/11/2008 for a period of one year. An APD extension was approved on 9/3/2009 for an additional one year. At this time Wexpro Company request an additional one year APD extension.

**Approved by the**  
**Utah Division of**  
**Oil, Gas and Mining**

**Date:** August 31, 2010

**By:**

<b>NAME (PLEASE PRINT)</b> Paul Jibson	<b>PHONE NUMBER</b> 307 922-5647	<b>TITLE</b> Permit Agent
<b>SIGNATURE</b> N/A		<b>DATE</b> 8/24/2010



## The Utah Division of Oil, Gas, and Mining

- State of Utah  
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

### Request for Permit Extension Validation Well Number 43047402780000

**API:** 43047402780000

**Well Name:** ISLAND U 89

**Location:** 0297 FSL 1940 FWL QTR SESW SEC 02 TWP 100S RNG 190E MER S

**Company Permit Issued to:** WEXPRO COMPANY

**Date Original Permit Issued:** 9/11/2008

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Signature:** Paul Jibson

**Date:** 8/24/2010

**Title:** Permit Agent **Representing:** WEXPRO COMPANY

**Date:** August 31, 2010

**By:** 

**RECEIVED** August 24, 2010



# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

September 23, 2011

Wexpro Company  
P.O. Box 458  
Rock Springs, WY 82902

Re: APD Rescinded – Island U 89, Sec. 2, T.10S, R.19E,  
Uintah County, Utah API No. 43-047-40278


Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on September 11, 2008. On September 3, 2009 and August 31, 2010 the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective September 23, 2011;

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

  
Diana Mason  
Environmental Scientist

cc: Well File  
SITLA, Ed Bonner  
Bureau of Land Management, Vernal

